
 PROJECT: Your Job Name Here PROJECT FILENAME: YOUR COMPANY NAME HE
 ADDRESS: 57 Blue Island St, Sebastian ARCHITECT:
 SECTIONS: ALL

Metal Panels Summary

50.00' X 16.00" Standing Seam Panel - 16" wide

LINEAR FEET	QUANTITY	% WASTE	TOTAL LN. FEET	SQUARE FEET
30'9"	16	1.8	492'0"	656.0
30'7"	1	2.4	30'7"	40.8
30'5"	1	2.5	30'5"	40.6
30'3"	1	2.5	30'3"	40.3
29'10"	3	2.5	89'6"	119.3
29'1"	1	2.6	29'1"	38.8
28'11"	1	2.6	28'11"	38.6
28'9"	1	2.6	28'9"	38.3
28'4"	3	2.6	85'0"	113.3
27'7"	1	2.0	27'7"	36.8
27'5"	1	2.7	27'5"	36.6
27'3"	1	2.7	27'3"	36.3
26'10"	19	9.5	509'10"	679.8
25'11"	1	2.9	25'11"	34.6
25'9"	1	2.9	25'9"	34.3
25'5"	4	2.9	101'8"	135.6
24'5"	1	3.1	24'5"	32.6
24'3"	2	3.1	48'6"	64.7
23'11"	4	3.1	95'8"	127.6
23'6"	1	3.2	23'6"	31.3
22'11"	1	3.3	22'11"	30.6
22'9"	2	27.0	45'6"	60.7
22'5"	4	3.3	89'8"	119.6
22'0"	2	3.0	44'0"	58.7
21'6"	1	3.5	21'6"	28.7
21'3"	13	4.2	276'3"	368.3
20'11"	7	10.3	146'5"	195.2
20'6"	1	3.6	20'6"	27.3
20'2"	1	50.8	20'2"	26.9
20'0"	1	4.3	20'0"	26.7
19'9"	1	3.8	19'9"	26.3
19'5"	7	3.8	135'11"	181.2
19'1"	1	3.9	19'1"	25.4
18'4"	1	4.1	18'4"	24.4
17'11"	12	9.1	215'0"	286.7
17'7"	1	4.2	17'7"	23.4
16'10"	1	3.9	16'10"	22.4
16'5"	9	4.5	147'9"	197.0
14'11"	10	5.5	149'2"	198.9
13'5"	9	5.6	120'9"	161.0
12'0"	10	6.8	120'0"	160.0
10'6"	9	7.1	94'6"	126.0
9'10"	24	0.2	236'0"	314.7
9'4"	13	16.0	121'4"	161.8
9'0"	13	9.3	117'0"	156.0
8'10"	2	43.8	17'8"	23.6
8'6"	21	5.5	178'6"	238.0
8'5"	1	13.6	8'5"	11.2

	7'6"	14	9.9	105'0"	140.0
	7'1"	2	9.9	14'2"	18.9
	6'0"	16	14.0	96'0"	128.0
	5'8"	2	12.4	11'4"	15.1
	4'6"	14	16.6	63'0"	84.0
	4'3"	2	16.5	8'6"	11.3
*	4'0"	27	51.9	108'0"	144.0

SUBTOTAL 319 Panels 4648'6" 6198.0

* Minimum Length Panel Breakout:

- 16 X ((1 X 3'0"))
- 2 X ((1 X 2'10"))
- 1 X ((1 X 2'3") + (1 X 1'6"))
- 6 X ((2 X 1'6"))
- 1 X ((1 X 1'6") + (1 X 1'5"))
- 1 X ((1 X 1'5"))

PAN. TOTAL 319 Panels 4648'6" 6198.0

Details Summary

DETAIL	UNITS	ORDER INFO
SS - Hip (10' pc)	23.0 PIECES	Zee Closure x2
SS - End or Head Wall (10' pc)	4.0 PIECES	Is Reglet required?
SS - Gable/Rake (10' pc)	6.0 PIECES	Zee & Cleat x1 ea
SS - Valley (10' pc)	11.0 PIECES	Off-Set Cleat x2
SS - Side Wall / "L" Flashing	2.0 PIECES	Is Reglet required?
SS - Extended Eave (10' pc)	35.0 PIECES	Add Cleat - IF Req'd
SS - Ridge (10' pc)	9.0 PIECES	Zee Closure x2

FLAT SHEET	UNITS	ORDER INFO
Flat Sheet - 48" x 120"	28 SHEETS	Qty req'd for trims

Items All Summary

ITEM	UNITS	ORDER INFO
Reglet - Wall Counter Flashing	6 Pc's	At Walls As Needed
Felt Underlayment	5729 Sq Ft	Exact SF - add 5-10%
7/8" Metal Stitch Screws	297 Ea	Adjust as required
1" Wood Pancake Screws	5697 Ea	Adjust as required
Pop Rivets (each)	404 Ea	Adjust as required
Sealant Tube (10 oz)	7 Tubes	Adjust as required
Butyl Tape (40'/45' Roll)	14 Rolls	Adjust as required
Cleat - Off-Set (10' pc)	22 Pc's	Valleys(x2) & ____ (?)
Cleat - Standard (10' pc)	6 Pc's	Rakes(x1) & ____ (?)
Zee Closure (10' pc)	76 Pc's	R&H/Rake/Walls/Trans

Extras Summary

DESCRIPTION	UNITS
INCLUDED ON QUOTE / ORDER ?	0 See List
Installation Manual	0 Ea
Color Chart	0 Ea
Paint Warranty	0 Ea
Weather Tight Warranty	0 Ea
Customer Approval Signature	0 Ea
Trim Sheet	0 Ea
Production Form	0 Ea
PANELS = Flat/Ribbed/Striated	0 Ea

Crate Charge	0 Ea
Delivery Charge	0 Ea
Fuel Surcharge	0 Ea
Any Other Items ?	0 Add

Total Surface Area = 5726.34 SQR FT